

DEMOCRATIC SOCIALIST REPUBLIC OF  
SRI LANKA  
MINISTRY OF HEALTH

**INSTALLATION OF SPUTUM COLLECTION  
BOOTHS - 40 NOS**

National Programme for Tuberculosis Control & Chest Diseases, Public Health  
Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.

**Contract No : NC/25/E04/020**

*Bidding Document*

National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw,  
Narahenpita, Colombo 05.

## INVITATION FOR BIDS (IFB)

### **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS**

**Contract No: NC/25/E04/020**

- 1] The Chairman, **Regional Procurement Committee (RPC)** on behalf of the **Ministry of Health** invites sealed **Bids** from eligible and qualified **Bidders** for **"INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS** as described below and estimated to basic cost (40 nos collection booth) of Rs. 9.5 Mn and the Construction Period is 35 days.
- 2] Bidding will be conducted through **National Competitive Bidding**.
- 3] To be eligible for Contract Award, the Successful Bidder shall not have been black listed and shall meet the requirement of CIDA Grade **C8, C7 and C6** specialty in building.
- 4] Interested Bidders may obtain further information from The Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No 555/5, 4<sup>th</sup> Floor, Elvitigala Mw, Narahenpita, Colombo 05, and inspect the Bidding Document at The Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No 555/5, 4<sup>th</sup> Floor, Elvitigala Mw, Narahenpita, Colombo 05, on working days between 9.00 a.m. to 3.00 p.m.
- 5] A complete set of **Bidding Document** in English language may be purchased by interested Bidders from the The Accountant, National Programme for Tuberculosis Control & Chest Diseases, on working days from .....2025 until..... 2025 between 9.00a.m. to 3.00p.m. or on the submission of a written request to the address below and upon payment of a non-refundable fee of **Rs. 3,500/-** to the National Programme for Tuberculosis Control & Chest Diseases Shroff.
- 6] **Bids** shall be delivered to the address below at or before ..... on..... Late **Bids** will be rejected. **Bids** will be opened soon after closing in the presence of the Bidders Representative who chooses to attend.
- 7] The Bids shall be valid up to **63 days** from the date bid opening date.
- 8] **Bids** shall be accompanied by a **Bid Security** amounting of **Rs.150,000/-**
- 9] Bid security shall be valid up to **91 days** from bid opening date ..... to ..... (Date)
- 10] Bidder should visit the site and get on idea of working environment.

The Address referred to above is:

The Director,  
National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex,  
No 555/5, 4th Floor,  
Elvitigala Mw,  
Narahenpita,  
Colombo 05,  
Tel- 011-2368274

## INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS

### Locations

- 1 DCC Galle
- 2 DCC Matale
- 3 DCC Matara
- 4 DCC Mullaithivu
- 5 DCC Puttalam
- 6 DCC Rathnapura
- 7 Prison - Welikada
- 8 PMCU Sedawatta
- 9 DH Piliyandala
- 10 DH Wethara
- 11 Colombo South Teaching Hospital
- 12 BH Homagama
- 13 DGH Awissawella
- 14 DGH Horana
- 15 DH Mathugama
- 16 BH Pimbura
- 17 BH Beruwala
- 18 Prison - Kaluthara
- 19 DGH Negombo
- 20 DH Biyagama
- 21 PMCU Sinharamulla
- 22 PMCU Hunupitiya
- 23 Prison - Mahara
- 24 Prison - Galle
- 25 BH Udugama
- 26 BH Elpitiya
- 27 DH Baddegama
- 28 DH Imaduwa
- 29 NH Kandy
- 30 BH Gampola
- 31 Prison - Kandy
- 32 DH Akurana
- 33 BH Theldeniya
- 34 DH Katupotha
- 35 BH Rideegama
- 36 DH Polgahawela
- 37 TH Rathnapura
- 38 BH Kalawana
- 39 BH Kahawatta
- 40 DH Maligawatta

Note : All bidders shall quote all 40 locations. Payment shall made after completion of location wise.

## CONTENTS

SECTION – 01	INSTRUCTION TO BIDDERS (ITB) .....	05
SECTION – 02	STANDARD FORMS	
	* Notes on Standard Forms .....	07
	* Letter of Acceptance.	08
	* Agreement .....	09
	* Performance Security.....	10
	* Form of Advance Payment Security .....	11
	* Retention Money Guarantee .....	12
SECTION – 03	CONDITIONS OF CONTRACT.....	14
SECTION – 04	FORM OF BID & QUALIFICATION INFORMATION ...	
	* Form of Bid .....	16
	* Qualification Information.....	17
SECTION – 05	SCHEDULES.....	19
SECTION – 06	SPECIFICATION .....	26
SECTION – 07	BILL OF QUANTITIES .....	28
SECTION – 08	FORM OF BID SECURITY.....	
SECTION – 09	DRAWINGS .....	

# INVITATION FOR BIDS (IFB)

**Ministry of Health**

Section – 01

## INSTRUCTION TO BIDDERS (ITB)

### INSTRUCTION TO BIDDERS (ITB)

Instruction to Bidders applicable to this **Contract** are those given in **Section 1** of the **Standard Bidding Document** for Procurement of Works – Minor Contracts, CIDA Publication No. **CIDA/SBD/03 (2<sup>nd</sup> Edition) January 2007 & the Addendum issued in January 2009** published by **Construction Industry Development Authority (CIDA)** “Savsiripaya”, 123, Wijerama Mawatha, Colombo 07.

This publication will not be issued with the **Bidding Document** and the **Bidder** is advised to Purchase it from **CIDA**.

Instruction to **Bidders** shall be read in conjunction with the schedule provided under **Section 5**. Schedule given which shall take precedence over instruction to **Bidders**.

Instruction to **Bidders** will not be part of the **Contract** & will cease to have effect once the contract is signed.



the  
IDA  
I in  
DA)

er is

nder

once

## Section – 02

### STANDARD FORMS (CONTRACT)

- \* *Letter of Acceptance*
- \* *Agreement*
- \* *Performance Security*
- \* *Form of Advance Payment Security*
- \* *Retention Money Guarantee*





### NOTES ON STANDARD FORMS

- **Bidders** shall submit the completed form of **Bid Security** / Bid Securing Declaration as appropriate in compliance with the requirement of the **Bidding Documents**.
- **Bidders** should not complete the **Form of Agreement** at the time of preparation of **Bids**.
- The successful **Bidder** will be required to sign the **Form of Agreement** after the award of **Contract**.
- Any corrections or modifications to the accepted **Bid** resulting from arithmetic corrections, acceptable deviations or quantity variations in accordance with the requirements of the **Bidding Documents** should be incorporated into the **Agreement**.
- The Form of **Performance Security** and **Form of Advance Payment Security** and **Form of Retention Money Guarantee** should not be completed by the **Bidders** at the time of preparation of **Bids**.
- The successful **Bidder** will be required to provide these securities in compliance with the requirements herein or as acceptable to the **Employer**

## FORM OF LETTER OF ACCEPTANCE

Date : .....

To : .....  
.....

*[Name & Address of the Contractor]*

This is to notify you that your **Bid** dated ..... for the construction and remedying defects of the **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS** (Contract No: NC/25/E04/020)" for the **Contract Price** of Rs..... as corrected in accordance with instructions to **Bidders** and is hereby accepted.

The **Adjudicator** shall be appointed by the **Construction Industry Development Authority (CIDA)**.

The **Start Date** shall be within 14 days from the date of issue of the **Letter of Acceptance**.

The amount **Performance Security** is ..... *[fill as per Clause 4.4 of Conditions of Contract]*

The **Performance Security** shall be submitted on or before ..... *[fill as per Clause 4.4 of Conditions of Contract]*

Authorized Signature : .....

Name & Title of Signature :

.....  
.....  
.....

National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex, No 555/5, 4th Floor,  
Elvitigala Mw, Narahenpita,  
Colombo 05.

## FORM OF AGREEMENT

This **Agreement** made the ..... [day] of ..... [month] 20..... between  
Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No  
555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05. [hereinafter called and referred to as  
"**the Employer**"] of the one part and .....  
[Hereinafter called and referred to as "**the Contractor**"] of the other part.

Whereas the employer desires that the **Contractor** execute the **INSTALLATION OF  
SPUTUM COLLECTION BOOTHS - 40 NOS** . [Hereinafter called and referred to as  
"**the Works**"] and the **Employer** has accept the **Bid** by the **Contractor** for the execution and  
completion of such **Works** and remedying of any effects therein.

### The Employer and the Contractor Agrees as Follows:

1. In this **Agreement** words and expressions shall have the same meanings as are  
respectively assigned to them in the **Contract** hereinafter referred to.
2. In consideration of the payments to be made by the **Employer** to the **Contractor** as  
indicated in this **Agreement**, the **Contractor** hereby covenants with the **Employer** to  
execute and complete the **Works** and remedy any defects therein, in conformity in all  
respects with the provisions of the **Contract**.
3. The **Employer** hereby covenants to pay the **Contractor** in consideration of the excited  
and completion of the **Works** and remedy any defects therein, the **Contract Price** or  
such other sum as may become payable under the provision of the **Contract** at the times  
and in the manner prescribed by the **Contract**.

In **Witness** where of the parties here to have caused this **Agreement** to be executed the  
day and year first before written in accordance with laws of Sri Lanka.

.....  
Authorized Signature of Contractor  
Common Seal

.....  
Authorized Signature of Employer  
Common Seal

In the Presence of :  
Witness :

1. Name and NIC No. : .....  
.....

2. Name and NIC No. : .....  
.....

Signature : .....

Signature : .....

Address : .....  
.....

Address : .....  
.....

## FORM OF PERFORMANCE SECURITY

(Unconditional)

.....  
.....  
[Insert issuing agency's Name and Address of issuing branch or office]

**Beneficiary:** Director, National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita,  
Colombo 05

**Date :** .....

**Performance Guarantee No. :** .....

We have been informed that .....[Name of Contractor] (hereinafter called "**the Contractor**") has entered into **Contract No. NC/25/E04/020** dated ..... with you, for the execution of **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS** [hereinafter called "**the Contract**"]

Furthermore, we understand that, according to the conditions of the **Contract**, a **Performance Guarantee** is required.

At the request of the **Contractor**, we.....  
[Name of the Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of Rupees..... [amount in words], (Rs. ....)[amount in figure] such sum being payable, upon receipt by us of your first demand in written accompanied by a written statement stating that the **Contractor** is in breach of its obligation(s) under the **Contract**, without your needing to prove or to show grounds for your demand or the sum specified therein.

This **Guarantee** shall expire, no later than the ..... day of ..... 20.....  
[28 days beyond the scheduled contract intended completion date] and any demand for payment under it must be received by us at this office on or before that date.

.....  
.....  
.....  
.....  
.....  
Signature(s)



## FORM OF ADVANCE PAYMENT SECURITY

[Insert Name and Address of issuing branch or office]

**Beneficiary :** Director, National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita,  
Colombo 05

**Date :** .....

**Advance Payment Guarantee No. :** .....

We have been informed that .....[Name of Contractor] (hereinafter called "**the Contractor**") has entered into **Contract No. NC/25/E04/020** dated ..... with you, for the execution of **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS "** [hereinafter called "**the Contract**"]

Furthermore, we understand that, according to the conditions of the **Contract**, an **Advance Payment** in the sum Rupees ..... [amount in words], (Rs. ....)[amount in figure] is to be made against an **Advance Payment Guarantee**.

At the request of the **Contractor**, we ..... [Name of the Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of Rupees ..... [amount in words], (Rs. ....)[amount in figure] upon receipt by us of your first demand in writing accompanied by a written statement stating that the **Contractor** is in breach of its obligation(s) in repayment of the **Advance Payment** under the **Contract**.

The maximum amount of this **Guarantee** shall be progressively reduced by the amount of the **Advance Payment repaid** by the **Contractor**.

This **Guarantee** shall expire, on ..... day of ..... 20..... [28 days beyond the intended completion date]

Consequently, we must receive any demand for payment under this **Guarantee** at this Office on or before that date.

.....  
Signature(s)

## FORM OF RETENTION MONEY GUARANTEE

[Insert Name and Address of issuing branch or office]

**Beneficiary :** Director, National Programme for Tuberculosis Control & Chest Diseases,  
Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita,  
Colombo 05

**Date :** .....

**Retention Money Guarantee No. :** .....

We have been informed that .....[Name of Contractor] (hereinafter called "**the Contractor**") has entered into **Contract No NC/25/E04/020** dated ..... with you, for the execution of **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS** [hereinafter called "**the Contract**"]. The work mainly consists of civil works whereas service for electrical and water supply will also complete under this **Contract**.

Furthermore, we understand that, according to the conditions of the **Contract**, when the works have being taken over and the first half of the **Retention Money** may be made against a **Retention Money Guarantee**.

At the request of the **Contractor**, we ..... [Name of the Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of Rupees .....[amount in words], (Rs. ....)[amount in figure] upon receipt by us of your first demand in writing accompanied by a written statement stating that the **Contractor** is in breach of its obligation(s) under the **Contract** because the **Contractor** has not attended to the defects in accordance with the **Contract**.

This **Guarantee** shall expire, at the latest, on ..... day of ..... 20..... [28 days after the end of the defects liability period].

Consequently, any demand for payment under this **Guarantee** must be received by us at this Office on or before that date.

.....  
Signature(s)

## Section – 03

# CONDITIONS OF CONTRACT

*Shall be read in Conjunction with the Section -05 Schedule in Volume 2, which shall take precedence over the Conditions of Contract*



### **CONDITIONS OF CONTRACT**

Conditions of **Contract** that will be applicable for this **Contract** shall be that given in **Section – 03** of the **Standard Bidding Document for Procurement of Works – Minor Contracts**, CIDA Publication No.CIDA/SBD/03 (2<sup>nd</sup> Edition) January 2007 and the **Addendum issued in January 2009**, published by **Construction Industry Development Authority (CIDA)** “Savsiripaya”; 123, Wijerama Mawatha, Colombo07.

This publication will not be issued with the **Bidding Document** and the **Bidder** is advised to purchase it from CIDA.

This conditions of **Contract** shall be read in conjunction with **Section 05** schedules attached herewith.

## Section – 04

### FORMS OF BID & QUALIFICATION INFORMATION

- \* *Form of Bid*

- \* Qualification Information

## FORM OF BID

**Name of Contract** : **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS**

**Name of Employer** : Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.

**Gentlemen,**

- 1] Having examined the Standard **Bidding Document** – Procurement of Works – Minor Contacts [CIDA/SBD/03 – Second Edition, January 2007], Schedules, Specifications, Drawings and Bills of Quantities and Addenda for the execution of the above named Works, We / I the undersigned, offer to execute and complete such **Works** and remedy any defect therein conformity with the aforesaid Condition of Contracts, Schedules, Specifications, Drawings and Bills of Quantities and Addenda for the sum of Sri Lankan Rupees ..... (LKRs. ....) or such other sums as may be ascertained in accordance with the said Conditions.
- 2] We / I acknowledge that the Schedule forms part of our **Bid**.
- 3] We / I undertake, if our **Bid** is accepted, to commence the Works as stipulated in the Schedule, and to complete the whole of the Works comprised in the Contract within the time stated in the Schedule.
- 4] We / I agree to abide by this **Bid** for the period stated in the Sub Clause 15 of Instruction to Bidders or any extended period and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
- 5] Unless and until a formal agreement is prepared and executed this **Bid** together with your written acceptance thereof, shall constitute a binding contract between us / me.
- 6] We / I understand that you are not bound to accept the lowest or any Bid you may receive.

Dated this ..... day of ..... in the capacity of ..... duly authorized to sign tenders for and on behalf of.....

Signature : .....

Address : .....

Witness : .....

## **QUALIFICATION INFORMATION**

(To be completed by the Bidder & Submitted by the Bid)

	<b>Eligibility Requirement</b>	<b>Bidder's Qualification</b>
<b><u>ICTAD Registration</u></b>		
Registration Number		
Grade	<b>C8, C7 and C6</b>	
Specialty	Civil Work, Building Work	
Expiry Date		

### **Black Listed Contractors**

Have you been declared as a defaulted Contractor by NPA or any other Agency	Yes / No
If yes Provide Details	
VAT Registration No.	
Legal Status	(Public Company / Private Company/ Partnership/ Sole Proprietor)

### **Qualification an experience of key staff**

<b>Category, Experience &amp; Qualifications</b>	<b>Required Nos.</b>	<b>Proposed by Bidder (Name, Experience &amp; Qualifications)</b>
<b>Technical Staff:</b> Technical Officer (NCT- Civil) – full time	1	

### **Similar Work Experience for Last Five Years**

<b>Work Description</b>	<b>Amount (Rs.)</b>
1.	
2.	
3.	
4.	
5.	

Signature of the Bidder : .....



Section – 05  
SCHEDULES



## SCHEDULE

ITB Clause	Conditions Of Contract	Item	Data
1	1.1.8	Employer is:	Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.
	1.1.10	Engineer is	Deputy Director General (Engineering), Ministry of Health,
1&13	1.1.21	Summary of Works	<p>The Work consist of <b>Improvement</b> works</p> <p>Work is located at the premises "<b>INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS</b>". Main scope of the contract is <b>INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS</b> Total works are hereinafter referred to as the "Work".</p> <p>Located at: - <b>INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS.</b></p>

### **INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS**

#### **Locations**

- 1 DCC Galle
- 2 DCC Matale
- 3 DCC Matara
- 4 DCC Mullaithivu
- 5 DCC Puttalam
- 6 DCC Rathnapura
- 7 Prison - Welikada
- 8 PMCU Sedawatta
- 9 DH Piliyandala
- 10 DH Wethara
- 11 Colombo South Teaching Hospital
- 12 BH Homagama
- 13 DGH Awissawella
- 14 DGH Horana
- 15 DH Mathugama
- 16 BH Pimbura
- 17 BH Beruwala
- 18 Prison - Kaluthara
- 19 DGH Negombo

- 21 PMCU Sinharamulla
- 22 PMCU Hunupitiya
- 23 Prison - Mahara
- 24 Prison - Galle
- 25 BH Udugama
- 26 BH Elpitiya
- 27 DH Baddegama
- 28 DH Imaduwa
- 29 NH Kandy
- 30 BH Gampola
- 31 Prison - Kandy
- 32 DH Akurana
- 33 BH Theldeniya
- 34 DH Katupotha
- 35 BH Rideegama
- 36 DH Polgahawela
- 37 TH Rathnapura
- 38 BH Kalawana
- 39 BH Kahawatta
- 40 DH Maligawatta

Note : All bidders shall quote all 40 locations. Payment shall made after completion of location wise.

**Contract Name : INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS**

**Contract No. : NC/25/E04/020**

- 1 1.1.14 Intended Completion Date Intended Completion Date is: 35 days from the Start Date.
- 2 Source of Funds Consolidated Fund of GOSL
- 3 Eligibility The Requirement is,  
Should be registered with the CIDA under the Grade **C8, C7 and C6.**
- 12 Documents Comprising the Bid "The Bid submitted by the Bidder shall comprise the following:  
a) Enclosed in the envelop marked as "Original"  
i) Complete Bidding Document with duly filled & signed form of Bid & qualification information with Priced Bill of Quantities.  
ii) Bid Security  
iii) Power of Attorney for signatory to the Bid  
iv) Any other information required to be completed and submitted by Bidders on specified in the schedule.



ITB Clause	Conditions Of Contract	Item	Data
			<p>b) Enclosed in the envelop marked as "copy".</p> <p>i) One copy of following Documents with duly filled and signed form of Bid and qualification information with priced Bill of Quantities.</p> <p>c) The Bidder may retain the other copy</p> <p>i) Complete Bidding Document with duly filled &amp; signed form of Bid &amp; qualification information with Priced Bill of Quantities.</p> <p>ii) Bid Security</p> <p>iii) Power of Attorney for signatory to the Bid</p> <p>iv) Any other information required to be completed and submitted by Bidders on specified in the schedule.</p> <p>d) All bidders shall quote all 40 locations.</p>
13	10.10	Price Adjustment	The Contract is not subjected to price adjustment.
15		Bid Validity	Bid Shall be remain valid for 63 days after the date of Bid Opening.
16		Bid Security	<p>Bid shall include a Bid Security For an amount of <b>Rs.150,000/- (One hundred and fifty Thousand Only)</b></p> <p>Issued by an agency acceptable to the Employer using the form for Bid Security (unconditional guarantee) included in section 9 Standard Forms.</p> <p>Remain valid till period of 91 days after the date of Bid opening.</p> <p>Security and Guarantees issued by the following institutions are acceptable :</p> <p>1) A <b>Commercial Bank</b> in <b>Sri Lanka</b> approved by <b>Central Bank</b> of the Sri Lanka and shall be addressed to the Secretary, Ministry of Health.</p> <p>2) A fixed deposit or a Pass Book of a Bank operating in Sri Lanka, deposits made in the name of the "The Director, National Programme for Tuberculosis Control &amp; Chest Diseases, Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.</p> <p>3) Construction Guarantee Fund</p> <p>4) Also, the Bidder can paid cash to the Shroff of National Programme for Tuberculosis Control &amp; Chest Diseases, Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.</p> <p>No interests will be paid on cash deposits.</p>

ITB Clause	Conditions Of Contract	Item	Data
31	4.4	Performance Security	Amount of Performance Security required is 5% of initial Contract Price.  The form acceptable is sample format which is in Volume 1 – Section 2, Standard Format.
	6.4	Late Completion	The amount to be paid is <b>0.05% of Initial Contract Price per day</b> , subjected to maximum of 5% of Initial Contract Price.
	8.1	Notification of Defects	The period for Defects Notification is 365 Days from Taking over.
	10.4	Retention	The Retention from each payment shall be 10% of the work done, as per the Interim Certificate.  The Limit of maximum amount of retention is 5% of Initial Contract Price.
32.0	10.12	Advance Payment	Advance Payment will be Paid with the amount of <b>20%</b> of the Initial Contract Price after furnishing a unconditional guarantees.
	13.1c	Insurance Third party	Minimum amount for third party insurance is <b>Rs.100,000/-</b> .
	13.1	Insurance for Employer & Contractor's Personnel	Minimum amount for Insurance for Employer & Contractor's Personnel is <b>Rs.100, 000/-</b> .
33	1.1.11	Adjudicator Resolution of Disputes	Fees and types of reimbursable expense to be paid to the Adjudicator shall be on a case basis and shall be shared by the Contractor and the Employer.

ITB Clause	Conditions Of Contract	Item	Data
		Payments of Variations	Engineer may order variation within 10% of the Contract Price

In fixing the appropriate new rates, mark up for overheads and profits shall be limited to maximum of 20% of the "Basic Cost" of such items. The Basic Cost means cost of materials, labour and equipment

In fixing such "Basic Cost" the Engineer shall use the rates for labour as given below and prices for materials and equipment shall be used the prevailing market prices.

Category	Rates (Rs.) per day
Skill labour	3670.00
Labour	2600.00

## ADDITIONAL CLAUSES

ITB Clause	Conditions Of Contract	Item	Data
15.1		Value Added Taxes (VAT)	<p>VAT component shall not be included in the rates. The amount written in the Form of Bid shall be without VAT.</p> <p>If Bidder is registered for VAT, the Bidder shall indicate the amount of VAT claimed separately at the end of the Bill of Quantities, in addition to the net value of the Bid, along with VAT registration number. The amount written on the Form of Bid shall be without VAT. Any Bidder who does not declare his VAT registration number will be liable for rejection of his Bid.</p> <p>If any Bidder is not registered for VAT, shall indicate the net value of the Bid. Under this category Bidder shall obtain a letter from the Commissioner of Inland Revenue Department, certifying the Company has not been registered for VAT, shall be attached to the Bid. Any Bidder who does not comply with this requirement will be liable for rejection of his Bid.</p> <p>The same VAT percentage will be applicable to any extra works and variation.</p>

Section – 06

## SPECIFICATIONS

2 S

## SPECIFICATIONS

The works under this contract shall be executed in accordance with the Specifications given in the following documents issued by the Institute for Construction Industry Development Authority (CIDA) "Savsiripaya", Wijerama mawatha, Colombo 07.

<u>Publication No.</u>	<u>Description</u>
SCA / 4 (Vol. I)	Specifications for Building Works, Vol (I), Sri Lanka, [3 <sup>rd</sup> Edition (Revised) – July 2004]
SCA / 4 (Vol. II)	Specifications for Building Works, Vol (II), Sri Lanka, [2 <sup>nd</sup> Edition (Revised) – October 2001]
SCA / 3 / 2	Specifications for Water Supply, Sewerage & Storm Water Drainage Works, Sri Lanka, [2 <sup>nd</sup> Edition (Revised) – April 2002]
SCA / 8	Specification for Electrical & Mechanical Works associated with Building and Civil Engineering, Sri Lanka, [2 <sup>nd</sup> Edition (Revised) – August 2000]

It is implied that the eligible Bidders are fully acquainted with the above documents and therefore, those will not be issued to the Bidders in this Bidding Document.

However the Bidders may purchase the same if necessary from CIDA. "Savsiripaya", Wijerama mawatha, Colombo 07.

Section – 07


## BILL OF QUANTITIES

29



## BOQ For Installation of Collection Booth at District Chest Clinic - Galle

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<p><i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i></p> <p><i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i></p> <p><i>Paint sample should be approved by Engineer</i></p> <p><i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i></p> <p><i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i></p> <p>Proposed Collection Booth</p> <p><b>1. DCC Galle</b></p>				
1.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
1.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
1.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
1.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
1.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
1.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



### BOQ For Installation of Collection Booth at District Chest Clinic - Galle

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
1.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2	-	
1.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
1.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
1.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
1.11	Supplying and fixing Plastic 1/2" Swan-necktap of "Solon" brand or approved equivalent.	1	nos		
1.12	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

*[Signature]*


## BOQ For Installation of Collection Booth at District Chest Clinic - Galle

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>1. DCC Galle</b>				
1.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
1.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
1.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
1.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
1.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
1.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



## BOQ For Installation of Collection Booth at District Chest Clinic - Matala

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<p><i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i></p> <p><i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i></p> <p><i>Paint sample should be approved by Engineer</i></p> <p><i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i></p> <p><i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i></p> <p>Proposed Collection Booth</p> <p><b>2. DCC Matala</b></p>				
2.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
2.2	concrete ( Grade 20) prepared at site manually,, floor area etc ....	0.2	m3		
2.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
2.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
2.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
2.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		





### BOQ For Installation of Collection Booth at District Chest Clinic - Matale

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
2.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
2.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
2.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
2.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
2.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
2.12	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at District Chest Clinic - Matara

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>3. DCC Matara</b>				
3.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
3.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
3.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
3.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
3.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
3.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		




# BOQ For Installation of Collection Booth at District Chest Clinic - Matara

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
3.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
3.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
3.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
3.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
3.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
3.12	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at District Chest Clinic - Mullaitivu

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<p><i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i></p> <p><i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i></p> <p><i>Paint sample should be approved by Engineer</i></p> <p><i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i></p> <p><i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i></p> <p>Proposed Collection Booth</p> <p><b>4. DCC Mullaitivu</b></p>				
4.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
4.2	concrete ( Grade 20) prepared at site manually,, floor area etc .....	0.2	m3		
4.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
4.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
4.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
4.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		




# BOQ For Installation of Collection Booth at District Chest Clinic - Mullaitivu

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
4.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
4.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
4.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
4.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
4.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
4.12	Allow provisional sum for: 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
Total Cost Carried to Summary					

*J*

8

**BOQ For Installation of Collection Booth at District Chest Clinic in Puttalam (5-DCC - Puttalam )**

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>5. DCC Puttalam</b>				
5.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
5.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
5.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
5.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
5.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
5.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



**BOQ For Installation of Collection Booth at District Chest Clinic in Puttalam (5-DCC  
- Puttalam )**

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
5.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
5.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
5.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
5.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
5.11	Supplying and fixing Plastic 1/2" Swan-necktap of "Salon" brand or approved equivalent.	1	nos		
5.12	Allow provisional sum for. 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

*J*



**BOQ For Installation of Collection Booth at District Chest Clinic in Rathnapura  
(6-DCC - Rathnapura )**

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>6. DCC Rathnapura</b>				
6.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
6.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
6.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
6.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
6.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
6.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



**BOQ For Installation of Collection Booth at District Chest Clinic in Rathnapura  
(6-DCC - Rathnapura )**

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
6.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
6.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
6.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
6.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
6.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
6.12	Allow provisional sum for. 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



### BOQ For Installation of Collection Booth at Prison - Welikada

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>7.Prison - Welikada</b>				
7.1	Site Clearing, Removing All kind of plants,, manual excavation for floor concrete.	1.5	L/day		
7.2	concrete ( Grade 20) prepared at site manually,, floor area etc ....	0.2	m3		
7.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
7.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
7.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
7.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		




### BOQ For Installation of Collection Booth at Prison - Welikada

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
7.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
7.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
7.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
7.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
7.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
7.12	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings, Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

## BOQ For Installation of Collection Booth at PMCU - Sedawatta

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>8.PMCU - Sedawatta</b>				
8.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
8.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
8.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
8.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
8.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
8.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		




### BOQ For Installation of Collection Booth at PMCU - Sedawatta

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
8.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
8.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
8.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
8.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
8.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
8.12	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at DH - Piliyandala

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<p><i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i></p> <p><i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i></p> <p><i>Paint sample should be approved by Engineer</i></p> <p><i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i></p> <p><i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i></p> <p>Proposed Collection Booth</p> <p><b>9.DH - Piliyandala</b></p>				
9.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
9.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
9.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
9.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
9.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
9.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		





### BOQ For Installation of Collection Booth at DH - Piliyandala

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
9.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
9.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
9.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
9.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
9.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
9.12	Allow provisional sum for. 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at DH - Wethara

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	<b>Proposed Collection Booth</b>				
	<b>10 .DH - Wethara</b>				
10.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
10.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
10.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
10.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
10.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
10.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



### BOQ For Installation of Collection Booth at DH - Wethara

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
10.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
10.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
10.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
10.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
10.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
10.12	Allow provisional sum for : 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

## BOQ For Installation of Collection Booth at Colombo South Teaching Hospital

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<p><i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i></p> <p><i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i></p> <p><i>Paint sample should be approved by Engineer</i></p> <p><i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i></p> <p><i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i></p> <p>Proposed Collection Booth</p> <p><b>11 .Colombo South Teaching Hospital</b></p>				
11.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
11.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
11.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
11.4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
11.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
11.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



## BOQ For Installation of Collection Booth at Colombo South Teaching Hospital

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
11.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
11.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
11.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
11.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
11.11	Supplying and fixing Plastic 1/2" Swan-necktapof "S-lon" brand or approved equivalent.	1	nos		
11.12	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at BH - Homagama

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
	<b>Proposed Collection Booth</b>				
	<b>12 .BH - Homagama</b>				
12.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
12.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
12.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
12.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
12.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
12.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		

### BOQ For Installation of Collection Booth at BH - Homagama

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
12.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
12.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
12.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
12.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
12.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
12.12	Allow provisional sum for. 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gully line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					



## BOQ For Installation of Collection Booth at DGH - Avissawella

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
	<b>Proposed Collection Booth</b>				
	<b>13 .DGH - Avissawella</b>				
13.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
13.2	concrete ( Grade 20) prepared at site manually., floor area etc ....	0.2	m3		
13.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
13.4	Supplying and fixing GI box bar-40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
13.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
13.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		




# BOQ For Installation of Collection Booth at DGH - Avissawella

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
13.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
13.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
13.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
13.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
13.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
13.12	Allow provisional sum for. 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

## BOQ For Installation of Collection Booth at DGH - Horana

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
	<b>Proposed Collection Booth</b>				
	<b>14 . DGH - Horana</b>				
14.1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.5	L day		
14.2	concrete ( Grade 20) prepared at site manually,, floor area etc ....	0.2	m3		
14.3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2	m2		
14.4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15	lm		
14.5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15	lm		
14.6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2	m2		



### BOQ For Installation of Collection Booth at DGH - Horana

Item	Description	Quantity	Unit	Rate (Rs.)	Amount(Rs.)
14.7	76x1.2mm thick natural aluminium partition frame is panelled with aluminium composite panel of total thickness 4mm, with both sides Polyester coated aluminium sheets of 0.2mm thick, 1220 mm height, completed with board joint stapled with necessary pop rivots, gasket & etc. and work complete in order	5	m2		
14.8	sashes 50x25mm 0.9mm thick natural aluminium door frame with double sash saloon hinged dual swing openable door with 50x26 Aluminium door section outer rail panelling with Polyester coated aluminium composite panel of 0.12 mm thick aluminium sheets both sides of total thickness 3mm at panel, rubber beading, gaskets, poprivots, with nut and approved hinges for saloon doors	1.5	m2		
14.9	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5	m2		
14.10	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00( sink frame paid separatly)	1	nos		
14.11	Supplying and fixing Plastic 1/2" Swan-necktap of "S-lon" brand or approved equivalent.	1	nos		
14.12	Allow provisional sum for: 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		20,000.00
<b>Total Cost Carried to Summary</b>					

