

Section – 05

SCHEDULES

SCHEDULE

ITB Clause	Conditions Of Contract	Item	Data
1	1.1.8	Employer is :	Director, National Programme for Tuberculosis Control & Chest Diseases, Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita, Colombo 05.
	1.1.10	Engineer is	Deputy Director General (Engineering), Ministry of Health,
1&13	1.1.21	Summary of Works	The Work consist of Improvement works Work is located at the premises "Ministry of Health". Main scope of the contract is INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS Total works are hereinafter referred to as the "Work". Located at: - AS per the Locations Contract Name : INSTALLATION OF SPUTUM COLLECTION BOOTHS - 40 NOS Contract No. : NC/26/E04/001
1	1.1.14	Intended Completion Date	Intended Completion Date is: 35 days from the Start Date.
2		Source of Funds	Consolidated Fund of GOSL
3		Eligibility	The Requirement is, Should be registered with the CIDA under the Grade " NC/26/E04/001 ".
12		Documents Comprising the Bid	"The Bid submitted by the Bidder shall comprise the following: a) Enclosed in the envelop marked as "Original" i) Complete Bidding Document with duly filled & signed form of Bid & qualification information with Priced Bill of Quantities. ii) Bid Security iii) Power of Attorney for signatory to the Bid iv) Any other information required to be completed and submitted by Bidders on specified in the schedule. V) Non-collusion declaration

ITB Clause	Conditions Of Contract	Item	Data
			b) Enclosed in the envelop marked as "Copy" i) One copy of following Documents with duly filled and signed form of Bid and qualification information with priced Bill of Quantities. c) The Bidder may retain the other copy of volume II of the Bidding Document.
13	10.10	Price Adjustment	The Contract is not subjected to price adjustment.
15		Bid Validity	Bid Shall be remain valid for 63 days after the date of Bid Opening.
16		Bid Security	Bid shall include a Bid Security For an amount of Rs.200,000/- (Two hundred thousand only) Issued by an agency acceptable to the Employer using the form for Bid Security (unconditional guarantee) included in section 9 Standard Forms. Remain valid till period of 91 days after the date of Bid opening. Security and Guarantees issued by the following institutions are acceptable : 1) A Commercial Bank in Sri Lanka approved by Central Bank of the Sri Lanka and shall be addressed to the Secretary, Ministry of Health. 2) A fixed deposit or a Pass Book of a Bank operating in Sri Lanka, deposits made in the name of the "The Secretary, Ministry of Health , "Suwasiripaya" No.385; Rev. Baddegama Wimalawansa Himi Mawatha, Colombo 10. 3) Construction Guarantee Fund 4) Also, the Bidder can paid cash to the Shroff of the Ministry of Health, "Suwasiripaya" No.385; Rev. Baddegama Wimalawansa Himi Mawatha, Colombo 10. No interests will be paid on cash deposits.

ITB Clause	Conditions Of Contract	Item	Data
31	4.4	Performance Security	Amount of Performance Security required is 5% of initial Contract Price. The form acceptable is sample format which is in Volume I – Section 2, Standard Format.
	6.4	Late Completion	The amount to be paid is 0.05% of Initial Contract Price per day , subjected to maximum of 5% of Initial Contract Price.
	8.1	Notification of Defects	The period for Defects Notification is 365 Days from Taking over.
	10.4	Retention	The Retention from each payment shall be 10% of the work done, as per the Interim Certificate. The Limit of maximum amount of retention is 5% of Initial Contract Price.
32.0	10.12	Advance Payment	Advance Payment will be Paid with the amount of 20% of the Initial Contract Price after furnishing a unconditional guarantees.
	13.1c	Insurance Third party	Minimum amount for third party insurance is Rs.100,000/- .
	13.1	Insurance for Employer & Contractor's Personnel	Minimum amount for Insurance for Employer & Contractor's Personnel is Rs.100, 000/- .
33	1.1.11	Adjudicator Resolution of Disputes	Fees and types of reimbursable expense to be paid to the Adjudicator shall be on a case basis and shall be shared by the Contractor and the Employer.
42.2			Certificate of Registration as an agent on behalf of the Tender(PCA 3 form) – certified copy

ITB Clause	Conditions Of Contract	Item	Data
		Payments of Variations	Engineer may order variation within 10% of the Contract Price

In fixing the appropriate new rates, mark up for overheads and profits shall be limited to maximum of 16% of the "Basic Cost" of such items. The Basic Cost means cost of materials, labour and equipment

In fixing such "Basic Cost" the Engineer shall use the rates for labour as given below and prices for materials and equipment shall be used the prevailing market prices.

Category	Rates (Rs.) per day
Skilled Labour	4250.00
Semi Skill labour	3250.00
Labour	2750.00

ADDITIONAL CLAUSES

ITB Clause	Conditions Of Contract	Item	Data
	15.1	Value Added Taxes (VAT)	VAT component shall not be included in the rates. The amount written in the Form of Bid shall be without VAT. If Bidder is registered for VAT, the Bidder shall indicate the amount of VAT claimed separately at the end of the Bill of Quantities, in addition to the net value of the Bid, along with VAT registration number. The amount written on the Form of Bid shall be without VAT. Any Bidder who does not declare his VAT registration number will be liable for rejection of his Bid. If any Bidder is not registered for VAT, shall indicate the net value of the Bid. Under this category Bidder shall obtain a letter from the Commissioner of Inland Revenue Department, certifying the Company has not been registered for VAT, shall be attached to the Bid. Any Bidder who does not comply with this requirement will be liable for rejection of his Bid. The same VAT percentage will be applicable to any extra works and variation.

Section – 06

SPECIFICATIONS

SPECIFICATIONS

The works under this contract shall be executed in accordance with the Specifications given in the following documents issued by the Institute for Construction Industry Development Authority (CIDA) "Savsiripaya", Wijerama mawatha, Colombo 07.

<u>Publication No.</u>	<u>Description</u>
SCA / 4 (Vol. I)	Specifications for Building Works, Vol (I), Sri Lanka, [3 rd Edition (Revised) – July 2004]
SCA / 4 (Vol. II)	Specifications for Building Works, Vol (II), Sri Lanka, [2 nd Edition (Revised) – October 2001]
SCA / 3 / 2	Specifications for Water Supply, Sewerage & Storm Water Drainage Works, Sri Lanka, [2 nd Edition (Revised) – April 2002]
SCA / 8	Specification for Electrical & Mechanical Works associated with Building and Civil Engineering, Sri Lanka, [2 nd Edition (Revised) – August 2000]

It is implied that the eligible Bidders are fully acquainted with the above documents and therefore, those will not be issued to the Bidders in this Bidding Document.

However the Bidders may purchase the same if necessary from CIDA. "Savsiripaya", Wijerama mawatha, Colombo 07.

Section – 07

BILL OF QUANTITIES

Installation of Sputum Collection Booth - BH Dehiattakandiya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
01 - BH Dehiattakandiya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc ----	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick AL Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Dehiattakandiya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate					

Installation of Sputum Collection Booth - BH Mahaoya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
02 - BH Mahaoya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Mahaoya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sam for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate					

Installation of Sputum Collection Booth - TH Batticaloa

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
03 - TH Batticaloa					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - TH Batticaloa

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Eravur

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
04 - BH Eravur					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L. day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Eravur

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.) (T-handle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DCC Batticaloa

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
05 - DCC Batticaloa					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DCC Batticaloa

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - TH Jaffna

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
06 - TH Jaffna					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - TH Jaffna

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for .		PS		28,000.00
	1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly.				
	2.)Arranging sample table.				
	3.)connecting the roofing sheet to existing frame.				
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Thelippalai

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
07 - BH Thelippalai					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions, And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Thelippalai

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Point Pedro

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
	08 - BH Point Pedro ✓				
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Point Pedro

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(T-handle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Kayts

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
09 - BH Kayts					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Couolumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Kayts

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Sammnthurai

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
10 - BH Sammnthurai					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick AL Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Samanthurai

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - AMH Kalmunai

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
11 - AMH Kalmunai					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - AMH Kalmunai

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Rikillagaskada

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
12 - BH Rikillagaskada					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc ----	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Rikillagaskada

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for , 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Dikoya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
13- BH Dikoya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Dikoya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for , 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DGH Trincomalee

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
14 - DGH Trincomalee					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DGH Trincomalee

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Kantale

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
15 - BH Kantale					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection ...

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt, Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - Prison Vavniya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
16 - Prison Vavniya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc ----	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - Prison Vavniya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					