

Installation of Sputum Collection Booth - DCC Vavniya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
17 - DCC Vavniya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame ,				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DCC Vavniya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DGH Mannar

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
18 - DGH Mannar					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L. day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DGH Mannar

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BM Murunkan

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
19 - BM Murunkan					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BM Murunkan

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Diyathalawa

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
20 - BH Diyathalawa					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick AL Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Diyathalawa

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Mahiyanganaya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
21 - BH Mahiyanganaya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Mahiyanganaya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame.				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for .		PS		28,000.00
	1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly.				
	2.)Arranging sample table.				
	3.)connecting the roofing sheet to existing frame.				
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Balapitiya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
22 - BH Balapitiya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Balapitiya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DH Padukka

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
23 - DH Padukka					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DH Padukka

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.) (Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for , 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Wellawaya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
24 - BH Wellawaya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Wellaway

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for , 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DH Buttala

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
25 - DH Buttala					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coslumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment,	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DH Buttala

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.) (T-handle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line - should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Medirigiriya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
26 - BH Medirigiriya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Medirigiriya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Welikanda

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
27 - BH Welikanda					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Welikanda

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gully line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Hingurakgoda

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
28 - BH Hingurakgoda					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Hingurakgoda

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose. all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for .	PS			28,000.00
	1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly.				
	2.)Arranging sample table.				
	3.)connecting the roofing sheet to existing frame.				
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Deniyaya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
29 - BH Deniyaya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc ----	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Deniyaya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(THandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Kamburupitiya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
30 - BH Kamburupitiya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc ----	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Kamburupitiya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DGH Matara

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
31 - DGH Matara					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually,, floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm. deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DGH Matara

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - DCC Kilinochchi

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
	32 - DCC Kilinochchi				
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - DCC Kilinochchi

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer, laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm, AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(THandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Mulankavil

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
— 33 - BH Mulankavil					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Mulankavil

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - PMCU Peliyagoda

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
34 - PMCU Peliyagoda					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Columns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - PMCU Peliyagoda

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent, including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Marawila

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
35 - BH Marawila					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete,	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Marawila

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for .		PS		28,000.00
	1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly.				
	2.)Arranging sample table.				
	3.)connecting the roofing sheet to existing frame.				
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - BH Anamaduwa

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
36 - BH Anamaduwa					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x 1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick AL Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - BH Anamaduwa

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - CD New Bazaar

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>				
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>				
	<i>Paint sample should be approved by Engineer</i>				
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>				
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>				
	- 37 - CD New Bazaar				
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick AL Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick, 76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - CD New Bazaar

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - CD Madampitiya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
38 - CD Madampitiya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L. day		
2	concrete (Grade 20) prepared at site manually,, floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - CD Madampitiya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)conncting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - CD Jinthupitiya

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
39 - CD Jinthupitiya					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L. day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al. Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL. BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - CD Jinthupitiya

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separately)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(THandle THandle)= 2,270	1.00	nos		
14	Allow provisional sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gulley line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booth - Slave Island

Item	Description	Quantity	Unit	Rate	Amount
	<i>All renovations are to be carried out disturbance to the hygienic condition maintained within the hospital premises. Safety precautions shall be included into relevant rates of items of the BOQ.</i>	Note			
	<i>Prior approval for materials shall be obtained from Engineer Before Commencing Work.</i>	Note			
	<i>Paint sample should be approved by Engineer</i>	Note			
	<i>Before leaving the site clean to the satisfaction of the Engineer at the completion of work.</i>	Note			
	<i>Any other Work except this Work sheet should be approved in formal way before commencing Work.</i>	Note			
40 -Slave Island					
1	Site Clearing, Removing All kind of plants, , manual excavation for floor concrete.	1.50	L day		
2	concrete (Grade 20) prepared at site manually., floor area etc	0.20	m3		
3	Shuttering for floor concrete dation with 1" thick rubber planking including dismantling	2.00	m2		
4	Supplying and fixing GI box bar 40mm x 40mm x1.4 mm thickness for of Coulumns(04 nos), roof, wash basin, sample table. Without Painting.	15.00	lm		
5	Painting two coats of enamel paint for columns including clearing surface before commencing painting work.	15.00	lm		
6	Rendering 1/2" thick in cement and sand 1:3 in concrete areas finished smooth with cement slurry and colour pigment.	2.00	m2		
	partition panels				
7	Supplying, Fabricating & Fixing of 4mm thick Al, Composite Cladding Boards in SINGLE SIDE of the existing partition frame work. (Rate Exclusive of Aluminium beadings, necessary EPDM rubber beadings, fasteners & etc.)	5.00	m2		
	partition frame				
8	Supplying, Fabricating and Installing of single row frame work with FULLY BOARDED panels in both sides for ALUMINIUM PARTITION consist of 1.2mm thick,76mm deep (width 23.0mm) (Alumex or eq.) Aluminium extrusions. And GI channel stiffener frame work enclosed in Aluminium frame work with an appropriate grid pattern not exceeding 1200mm in both vertical & horizontal directions suited to the available space and additional GI channel bracings placed in 600mm centers at vertical direction. Rate inclusive of Aluminium beadings (including necessary EPDM rubber beadings) necessary fasteners etc. (PANNEL BOARDS PAID SEPERATLY)	4.50	m2		
	double door panel				

Installation of Sputum Collection Booth - Slave Island

Item	Description	Quantity	Unit	Rate	Amount
9	Supplying, Fabricating and Installing of Natural Aluminium Double sashed Swing Door (sash only) for 1.6mm thick 100mm deep door frames with suitable wool felt. Rate inclusive of necessary fasteners and hinges(saloon hinged) (Union or equivalent 102x76x2 mm) etc.(Glass/ Board, Door closers, door locks and door handles paid separately).	1.50	m2		
	double door frame				
10	Supplying, Fabricating and Installing 1.6mm thick 45mm X 100mm (depth) Aluminium outer door frame for double sash Swing door. Rate inclusive of necessary fasteners and etc.(Door sashes, Door closers, door locks and door handles paid separately) (Alumex extrusion No. 100D-3005 or equivalent) - Refer K001 to K016 for glass & boards, k017 to K051 for louvers, K743-K764 for accessories, K197-K206 for door sash-	2.40	m		
11	Supply and fix zinc alum profile roofing colour sheet with screws and washer , laid on existing purlings with joints to be properly connected with an adequate side lap to ensure water tightness along the entire length and complete to working order.(Thk. 0.47mm , AZ 150)	5.00	m2		
12	Supply and fix 460mmx 380mm stainless steel 0.8mm thick shiny finish kitchen sink (304) with single bowl an authorized agent. including PVC bottle trap and water connection with flexible hose, all complete to working order.(Swannecktap paid separately.) Prime cost of the kitchen sink is Rs.10,750.00(sink frame paid separatly)	1.00	nos		
13	Supplying & fixing Plastic Swan-neck tap DN15 (1/2 inch) (T-Handle) (S-Lon or Equivalent.) Prime Cost of, Plastic Swan Tap DN15 (1/2 inch) (S-Lon or Equi.)(Thandle THandle)= 2,270	1.00	nos		
14	Allow provisonal sum for . 1.)Supplying water line and supply line including all fittings. Waste line should connecting to existing gully line properly. 2.)Arranging sample table. 3.)connecting the roofing sheet to existing frame.		PS		28,000.00
Total Cost Estimate Carried to Summary					

Installation of Sputum Collection Booths - 40 nos

		Rs.	Cts.
1	BH Dehiattakandiya		
2	BH Mahaoya		
3	TH Batticaloa		
4	BH Eravur		
5	DCC Batticaloa		
6	TH Jaffna		
7	BH Thelippalai		
8	BH Poinr Pedro		
9	BH Kayts		
10	BH Sammanthurai		
11	AMH Kalmunai		
12	BH Rikillagaskada		
13	BH Dikoya		
14	DGH Trincomalee		
15	BH Kantale		
16	Prison vavuniya		
17	DCC Vavuniya		
18	DGH Mannar		
19	BH Murunkan		
20	BH Diyatalawa		
21	BH Mahiyanganaya		
22	BH Balapitiya		
23	DH Padukka		
24	BH Wellawaya		
25	DH Buttala		
26	BH Medirigiriya		
27	BH Welikanda		
28	BH Higurakgoda		
29	BH Deniyaya		
30	BH Kamburupitiya		
31	DGH Matara		
32	DCC Kilinochchi		
33	BH Mulankavil		
34	PMCU Peliyagoda		
35	BH Marawila		
36	BH Anamaduwa		
37	CD New Bazaar		
38	CH Madampitiya		
39	CD Jinthupitiya		
40	CD Slave Island		
Total Cost Carried to Main summary			

B.O.Q - MAIN SUMMARY

		Amount	
		Rs.	Cts.
Bring Forward to Main Summary (total of 40 nos)	=		
Less Provisional Sum (40x rs 20000.00)	=		1,120,000.00
Sub Total - I	=		
Discount if any (..... %)	=		
Sub Total - II	=		
Add Provisional Sum (40x rs 20000.00)	=		1,120,000.00
<i>Bid Amount before VAT carried to Form of Bid</i>	=		
Add 18% VAT	=		
Total after VAT	=		

Bid amount before VAT in Words

Rupees.....
 & Cents only

Bidder VAT Register No. (if any) :

.....
 Signature of Bidder

.....
 Date

.....
 Name, Address & NIC No. of Bidder

.....
 Signature of Witness (1)

.....
 Signature of Witness (2)

.....
 Name, Address & NIC No. of Witness

.....
 Name, Address & NIC No. of Witness

Date :

Date :

Section – 08

STANDARD FORMS (BID)

FORM OF BID SECURITY

.....
.....
[Insert issuing agency's Name and Address of issuing branch or office]

Beneficiary: Director, National Programme for Tuberculosis Control & Chest Diseases,
Public Health Complex, No 555/5, 4th Floor, Elvitigala Mw, Narahenpita,
Colombo 05.

Date:

Bid Guarantee No. :

We have been informed that [Name
of Bidder] (hereinafter called "**the Bidder**") has submitted to you its Bid dated
(hereinafter called "**the Bid**") for the execution of **INSTALLATION OF SPUTUM
COLLECTION BOOTHS - 40 NOS** [hereinafter called "**the Contract**"] under Invitation
for Bids No. (the IFB)

Furthermore, we understand that, according to the conditions, Bids must be supported
by a **Bid Guarantee**.

At the request of the **Bidder**, we
[Name of the Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding
in total an amount of Rupees
.....[amount in words], (Rs.)[amount in
figure] upon receipt by us of your first demand in written accompanied by a written statement
stating that the **Bidder** is in breach of its obligation(s) under the **Bid** conditions, because the
Bidder :

- a) has withdrawn its Bid during the period of Bid Validity specified; or
- b) does not accept the correction of errors in accordance with the Instructions to Bidders
("the ITB") or
- c) having been notified of the acceptance of its Bid by the Employer during the period of
Bid validity, (i) fails or refuses to execute the Contract Form, if required or (ii) fails or
refuses to furnish the Performance Security, in accordance with the ITB.

This **Guarantee** shall expire, (a) if the Bidder is the successful bidder, upon our receipt
of copies of the Contract signed by the Bidder and of the Performance Security issued to you
by the Bidder; or (b) if the Bidder is not the successful Bidder, upon the earlier of (i) our
receipt of a copy of your notification to the Bidder that the Bidder was unsuccessful, otherwise
it will remain in force up to (date)

Consequently, any demand for payment under this Guarantee must be received by us at
the office on or before that date.

.....
Signature(s)

11 34

Non-collusion Declaration

I, the undersigned bidder/ bidder's representative/ bidder's agent, honestly, truthfully and Solemnly declare that;

(a) I, nor any other member, agent or representative of the firm/ company/ corporation/ partnership/ sole proprietorship that I represent, have entered into any combination, collusion or similar agreement with any person in connection with the prices to be submitted by any

Person with respect to the invitation for bid;

(b) I, nor any person who represents me have acted to prevent any person from submitting a bid or to induce any person to refrain from submitting a bid in connection with the intention for bid (Bid No. NC/26/E04/001);

(c) This bid is not submitted in collusion with any other bid and is not made pursuant to any agreement, understanding or association with any other person in relation to such bid.

I declare that, I have not received and will not accept any discount, fee, reward, commission or anything of value, directly or indirectly, from any person, company or corporation in connection with the submission of this bid.

I further declare that, I have not given and will not give any discount, fee, reward, commission or anything of value, directly or indirectly, to any person, company or corporation in connection with the submission of this bid.

I, taking full responsibility for ensuring the absence of collusion, hereby pledge to abide by fair and ethical competitive practices throughout the entire procurement process and to fully comply with the relevant Procurement Guidelines issued by the National Procurement Commission.

I hereby declare that all the statements made by me above are true and correct.

.....

Signature of the Declarant



TB sampling cabin

Date - 20 May 2025

